

Sl. No.	Description of work	Approximate quantity	Unit
<i>Constructing Sweepers' Quarters 1 Unit at Channarayana Railway Station.</i>			
1.	Earthwork excavation in all soils and filling in basement ..	400 C.ft.	1,000 C.ft.
2.	Concrete broken granite stone jelly in lime mortar ..	163 "	100 "
3.	Burnt brick in chunam mortar ..	354 "	100 "
4.	Burnt brick in mud ..	535 "	100 "
5.	Burnt stone slabs one line dressed and fixed in chunam mortar ..	61 S.ft.	S.ft.
6.	Teakwood doors with battened shutters 1" thick, hinges, tower bolts, etc., complete ..	18 "	"
7.	Teakwood windows with 1" thick battened shutters in four halves, $\frac{3}{4}$ " sq. M. S. bars fixed at not more than 4" centre to centre, rings, hooks, etc., complete ..	12 "	"
8.	Teakwood ventilators with 1" thick battened shutters, $\frac{3}{4}$ " sq. M. S. bars, rings, hooks, etc., complete ..	6 "	"
9.	Teakwood wrought and put up including wood oiling, two coats ..	17 C.ft.	C.ft.
10.	Roofing with first class Mangalore pattern Yelahanka tiles on teak reapers 2" x 1" including wood oiling to reapers and providing chunam borders, teakwood wind-ties, etc., complete, R.M.C. will be given for tiles from Yelahanka ..	384 S.ft.	100 S.ft.
11.	Ridge tiles set in mortar and cement pointed. R.M.C. will be given for tiles ..	21 R.ft.	R.ft.
12.	Chunam plastering ..	1,465 S.ft.	100 S.ft.
13.	White and colour washing, two coats ..	1,465 "	100 "
14.	Supplying and fixing granite stone pestle and mortar ..	1 No.	Each
15.	Flooring with 4" thick concrete broken jelly in chunam mortar and plastered over with $\frac{1}{2}$ " thick cement ..	142 S.ft.	100 S.ft.
16.	Providing and fixing smoke tiles in mortar and cement pointed. R.M.C. will be given for tiles ..	2 Nos.	Each
17.	Providing ovens ..	1 No.	"
18.	Silicate chalcote painting, two coats ..	100 S.ft.	100 S.ft.
19.	Plain eave board 9" wide $\frac{3}{4}$ " thick including painting and fixing complete ..	36 R.ft.	R.ft.
20.	Providing T. W. pendants ..	4 Nos.	Each
21.	Do T. W. Finials ..	2 "	"
22.	Do 'U' shaped cement drain 4 $\frac{1}{2}$ " wide including cement plastering, complete ..	12 R.ft.	R.ft.

Note.—Departmental materials such as Teakwood doors, scantlings, tiles, slabs, etc., issued to be used on works.

D. V. NARASIMHA RAO,
District Engineer.

OFFICE OF THE DEPUTY COMMISSIONER, HASSAN DISTRICT.

Notification No. C. 5027-38, dated the 27th August 1939.

It is hereby notified for the information of the public that the Travellers' Bungalows at the undermentioned places will be reserved for the use of the Dewan of Mysore on the dates noted against each, in connection with his tour in Hassan District.

- | | | | |
|----|-----------------|---------|---|
| 1. | Chennarayapatna | | 21st September 1939. |
| 2. | Hole-Narsipur | | 21st September 1939. |
| 3. | Hassan | | 21st September 1939 to 23rd September 1939 (both days inclusive.) |
| 4. | Belur | | 23rd September 1939. |
| 5. | Arsikere | | 24th September 1939. |

T. RAMAIA,
Deputy Commissioner.